

TEST REPORT



Report No.:BVIPL:ADMIXTURE: HL/2216/1/2025/2
Test order dated: 23.01.2025

Date:31.01.2025
Page: 1 of 1

BNR Enterprises

Survey No 64/1, 64/2 & 643/3
Plot No 48, Pasumamula Road Peddamberpet Vill
Hayathnagar Mandal Ranga Reddy District – 501505.

CHEMICAL TESTING Building Materials

UNIFORMITY TEST REPORT ON ADMIXTURE SAMPLE

Source of Sample : Sample supplied by the customer
Customer's Reference : E-mail dated 22.01.2025
Condition of samples : Satisfactory
UIN No. : 25002224
Project : Not Furnished
Product Name # : Belpast 316 (PCE Base)
Period of test : 30.01.2025 to 31.01.2025
Test Method : IS : 9103-1999 (Reaffirmed 2018) and IS : 6925 – 1973 (Reaffirmed 2018)

Sl No	Test Conducted	Results	Requirements as per Table 2 of IS:9103-1999
1	Ash Content (AC) (% by mass)	1.19	$0.95 T \leq AC < 1.05 T$ T-manufacturer's stated value
2	Dry material content (DMC) (% by mass)	16.65	$0.95 T \leq DMC < 1.05 T$ T-manufacturer's stated value
3	Water Soluble Chloride (% by mass)	0.017	Within 10% of the value or within 0.2% whichever is greater as stated by the manufacturer
4	pH (Temperature @ 25° C)	5.38	Minimum 6.0
5	Relative Density	1.055	Within 0.02 of the value stated by the manufacturer

As furnished by the customer

- Note:
1. The results relate only to the items tested.
 2. Report shall not be reproduced, except in full, without the written approval of the lab.
 3. Any correction invalidates this report.

for BUREAU VERITAS (INDIA) PRIVATE LIMITED
Construction Services Laboratory

Bhagwan S
31/01/2025

****END OF THE REPORT****

BHAGWAN.S

Assistant Manager-Chemical Lab
Authorized Signatory